

# PEERBOLTE CREATIVE LLC

---

February 13, 2017

TO: Bruce Gibson, CEM, BEP  
Assistant Director of Facilities  
FR: David Peerbolte  
Peerbolte Creative  
RE: Lee's Summit West  
Auditorium Lighting Update

- 1) Required conduit and back boxes in the balcony vestibules will be run by Lee's Summit R-7. Low voltage wire will be supplied by the lighting contractor and pulled by Lee's Summit R-7. Low voltage wire supplied by theatre contractor shall be plenum rated.
- 2) Lee's Summit R-7 will supply and run all conduits and make load terminations. Lighting contractor will supply all specialty back boxes and low voltage wire. All low voltage terminations will be accomplished by the lighting contractor.
- 3) Wireless DMX can be bid as an alternate for the DMX box on the loading rail.
- 4) Bid date has been changed to 3PM on March 1.
- 5) Existing boxes in the Pit and Stage Left wing can be used for the new devices to be installed in those locations. All abandoned slots shall be covered with blank face plates.
- 6) The devices to be installed in the ADA location shall be broken into two single gang plates and installed in the two floor pockets in this area. The two DMX-in jacks shall be on one face plate. The net jack shall be on a second face plate.